

**Lamp Circuit Power Test Report**

To : GE Lighting Co., Ltd. Tel : --  
1975, Noble Road, East Cleveland, OH, 4412 Fax : --  
– 6300, USA

Attn : --

Supplier : Sichuan Hongrui Electric Co., Ltd.

Supplier address : Mianyang Export Processing Zone, High-Tech Park,  
Mianyang, Sichuan, China

Product type : ERA17P40VDSG44; ERA17P40VDSG44F;  
ERA17P40VDSG66; ERA17P40VDSG66F;  
ERA17P40VDBK44; ERA17P40VDBK44F;  
ERA17P40VDBK66; ERA17P40VDBK66F

Applicable standards : --

Samples picked by : Manufacture/Supplier

Samples received in DEKRA : 2018-01

Laboratory on :

Amount of samples : 10 samples on : --

Clauses checked : Refer to the following Test Items

Tests performed : LCP on each sample

This Document includes : 9 pages

Date of Testing : 2018-02-07

**DEKRA Testing and Certification (Shanghai) Ltd**

10/F, #250, Jiangchangsang Road building  
16 Headquarter Economy Park  
Shibei Hi-Tech Park, Zhabei District  
Shanghai, 200233, P.R. China  
Tel: +86 21 60567666  
Fax: F + 86 21 6056 7555

**PRODUCT DATA**

			Remarks
Product description	:	LED street luminaire	--
Type	:	ERRA17P40VDSG44; ERRA17P40VDSG44F; ERRA17P40VDSG66; ERRA17P40VDSG66F; ERRA17P40VDBK44; ERRA17P40VDBK44F; ERRA17P40VDBK66; ERRA17P40VDBK66F	--
Lamp Cap	:	--	--
Rated Wattage	:	17 W	--
Rated Luminousflux	:	--	--
Rated Voltage	:	240 V~	--
Rated CCT	:	--	--

Note. All models have the same mechanical and electrical construction.

**SAMPLE PICTURE**



Over view



Overview

**SAMPLE PICTURE**



LED module

**TEST ITEMS**

NO	CONTENTS	
1	Electrical characteristics Measurements	<input checked="" type="checkbox"/>

**TEST RESULTS DESCRIPTION**

Electrical characteristics Measurements

Sample 1

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.079	17.1	0.902	5 minutes
2	240.0	0.079	17.1	0.902	15 minutes
3	240.0	0.079	17.1	0.902	30 minutes

Sample 2

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.08	17.3	0.902	5 minutes
2	240.0	0.08	17.3	0.902	15 minutes
3	240.0	0.08	17.3	0.902	30 minutes

Sample 3

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.08	17.3	0.901	5 minutes
2	240.0	0.08	17.3	0.901	15 minutes
3	240.0	0.08	17.3	0.901	30 minutes

Sample 4

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.078	17.2	0.915	5 minutes
2	240.0	0.079	17.3	0.915	15 minutes
3	240.0	0.079	17.3	0.915	30 minutes

## Sample 5

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.08	17.2	0.899	5 minutes
2	240.0	0.08	17.2	0.899	15 minutes
3	240.0	0.08	17.2	0.899	30 minutes

## Sample 6

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.08	17.3	0.907	5 minutes
2	240.0	0.08	17.3	0.907	15 minutes
3	240.0	0.08	17.3	0.907	30 minutes

## Sample 7

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.079	17.3	0.912	5 minutes
2	240.0	0.078	17.3	0.912	15 minutes
3	240.0	0.079	17.3	0.912	30 minutes

## Sample 8

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.08	17.4	0.906	5 minutes
2	240.0	0.08	17.4	0.906	15 minutes
3	240.0	0.08	17.4	0.906	30 minutes

## Sample 9

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.079	17.3	0.912	5 minutes
2	240.0	0.079	17.3	0.912	15 minutes
3	240.0	0.079	17.3	0.912	30 minutes

## Sample 10

No	Test Voltage (Vac)	Test Current (A)	LCP (W)	Power Factor	Buring on time before testing
1	240.0	0.08	17.3	0.901	5 minutes
2	240.0	0.08	17.3	0.901	15 minutes
3	240.0	0.08	17.3	0.901	30 minutes

## Note.

The test samples were connected to the clean power source and supplied with voltage as listed in above "test result description". The test samples were operated until the conditions of overall temperature equilibrium were established or at least 4 hours in stabilized operation with the supplied sources. Then the total power consumption measurements have been taken by power meter.



Please note that every statement made in this report is only valid for the samples tested and reported herein,

Trusting to have informed you sufficiently, we remain,  
With best regards

DEKRA Testing and Certification (Shanghai) Ltd.


**Engineer name** : Li Peng

**Engineer signature** :



**Reviewed by** : Wesley Xu

**Reviewer signature** :



-----the end-----