

## Vipac Engineers & Scientists Limited

2 Sirius Road, Lane Cove, NSW, AUSTRALIA, 2066  
A.B.N. 33 005 453 627

t. (+61 2) 9422 4222 f. (+61 2) 9420 5911  
e. [sydneylabs@vipac.com.au](mailto:sydneylabs@vipac.com.au) w. [www.vipac.com.au](http://www.vipac.com.au)  
ISO9001 Certified Quality Management System

## Electrical Load Test Certificate – UPS Power Consumption Measurement

<b>CERTIFICATE NO:</b> 20E-12-0173-COC-267240-1		<b>Purchase Order:</b> 4510316048
<b>PREPARED FOR:</b> Roads & Maritime Services Level 2, Pod C 99 Phillip Street Parramatta NSW 2124 <b>Contact: Trevor Johnson</b> <b>Phone: +61 2 8837 0273</b> <b>Fax: +61 2 8837 0020</b> <b>Email: Trevor.JOHNSON@rms.nsw.gov.au</b>		<b>PREPARED BY:</b> Sydney Laboratories Vipac Engineers & Scientists Ltd. 2 Sirius Road LANE COVE, NSW, AUSTRALIA, 2066 <b>Phone: +61 2 9422 4222</b> <b>Fax: +61 2 9420 5911</b> <b>Email: sydneylabs@vipac.com.au</b>
<b>AUTHOR:</b> John Wang Date: 31 Oct 2012		Electrical Safety Team Leader
<b>REVIEWED BY:</b> James Emery Date: 31 Oct 2012		Electrical Safety Electrician
<b>ISSUED BY:</b> John Duffett Date: 31 Oct 2012		Assistant Test Facility Manager & QA Representative
<b>REVISION HISTORY:</b>		
<b>Revision No.</b>	<b>Date Issued:</b>	<b>Reason/Comments:</b>
00	31 October 2012	Initial Issue
01	31 October 2012	Editorial revision
<b>DISTRIBUTION:</b>		
<b>Copy No.</b> _____		<b>Location</b>
1		Project
2	Uncontrolled Copy	Client (PDF Format)
<b>KEYWORDS:</b> UPS, Power, Consumption		


TEST ITEM DESCRIPTION	
<b>Name</b>	Alpha UPS for Traffic Signal Lanterns
<b>Model</b>	FXM2000
<b>Serial Number</b>	F31404

**TEST REQUIREMENT**

**Parameter**

Measurement of power consumption at both the input and output of the tested UPS in floating charging mode with a resistive load connected to UPS.

**Configuration**



**TEST EQUIPMENT**

Equipment	Vipac asset code	Brand and model	Serial number	Calibration due date
Digital power meter for input measurement	15773	Yokogawa WT210	91M329675	25 September 2013
Digital power meter for output measurement	19976	LEM Analyst 2050	15812	05 September 2013
Voltage stabiliser	30188	Power Electronics EMA-50	87241-1	-

RESULTS					
	Voltage (V)	Current (A)	Actual power (W)	Apparent power (VA)	Power factor
UPS Input	240.4	4.69	1001.9	1131.8	0.887
UPS Output	235.9	3.92	920	940	0.979

Parameters indicated on UPS when the above measurement was taken	
Input voltage: 236.5V	Output voltage: 235.5V
Output current: 3.8A	Output power: 894VA
Battery voltage: 53.6V	Charging current: 0.0A
Battery temperature: 18°C	Frequency: 50.0Hz

**Test environment:**

Testing performed at indoor area

Room temperature: 23.9°C

Relative humidity: 57.5%